

PROJECT
ADDRESS
Date of submission
Date of plans
Comments
TOTAL BASE BID



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAST E	QTY.	UNIT W/ WAST E	UNIT COST
03 00 00 CONCRETE									
PAVING									
Interlocking Concrete paving stone									
1	L-1.0	1/L-4.0		IPS Paving	426	10%	4 69	SF	
2	L-1.0	1/L-4.0		1" angular concrete sand as per detail 1/L-4.0	426	10%	4 69	SF	
3	L-1.0	1/L-4.0		8" class II base rock @ 95% rel.compaction O/-6" subgrade scarify and comapct to 90% rel.compaction	284	10%	3 13	CF	
4	L-1.0	1/L-4.0		18" wide concrete band edge restraint	211	10%	2 32	CF	
Colored concrete paving									
5	L-1.0	2/L-4.0		4" thick concrete paving #4 bars @ 18" O.C each way Color:Davis-Sandstone Finish:Light sand	640	10%	7 04	SF	
6	L-1.0	2/L-4.0		4" Class II base o/-compacted subgrade	211	10%	2 32	CF	
Natural stone paver									
7	A-1.3 or L-1.0	3/L-4.0		2" Thick natural stone paver	202	10%	2 23	SF	
8	A-1.3 or L-1.0	3/L-4.0		4" Class II base o/-compacted subgrade	67	10%	7 3	CF	
9	A-1.3 or L-1.0	3/L-4.0		3/8" Max.gravel infill	132	10%	1 45	SF	
10	A-1.3 or L-1.0	3/L-4.0		2"x6" Composite wood edging	152	10%	1 67	LF	
Granite paving									
11	A-1.3 or L-1.0	4/L-4.0		4" thick granite concrete material	255	10%	2 81	SF	
12	A-1.3 or L-1.0	4/L-4.0		6" Class II base rock @ 909% rel compaction o/-compacted subgrade	128	10%	1 40	CF	
13	A-1.3 or L-1.0	4/L-4.0		2x10 composite edge restraint Secure to ground w/ 1x2x18 lg.stakes @ 24" O.C	143	10%	1 57	LF	
Concrete sidewalk									
14	A-1.3	6/A-1.6		4" Concrete sidewalk	763	10%	8 39	SF	
Driveway paving									
15	A-1.3	3/A-1.6		4" Porous concrete	####	10%	####	SF	
16	A-1.3	3/A-1.6		2" Asphaltic concrete	####	10%	####	SF	
17	A-1.3	3/A-1.6		6" Class II aggregate	####	10%	####	CF	
18	A-1.3	3/A-1.6		4'-2 1/2" Class II aggregate	####	10%	####	CF	
Concrete paving									
19	A-1.3 or L-1.0	2/L-4.0		4" thick concrete paving #4 bars @ 18" O.C each way	164	10%	1 80	SF	
20	A-1.3 or L-1.0	2/L-4.0		4" Class II base o/-compacted subgrade	54	10%	6 0	CF	
Guest parking paving									
21	A-1.3	Note-6/A-1.3 & 3/A-1.6		4" Porous concrete	331	10%	3 64	SF	
22	A-1.3	Note-6/A-1.3 & 3/A-1.6		2" Asphaltic concrete	331	10%	3 64	SF	
23	A-1.3	Note-6/A-1.3 & 3/A-1.6		6" Class II aggregate	166	10%	1 82	CF	

24	A-1.3	Note-6/A-1.3 & 3/A-1.6	4'-2 1/2" Class II aggregate	####	10%	####	CF	
			Note: No detail is given for guest parking so we consider it as driveway parking & same detail is applied kindly advise if wrong					
25	A-1.3	Note-14/A-1.3	New driveway New driveway Note: No detail given kindly check it	473	10%	5 20	SF	
			Sub Total					
			SITE CONCRETE					
26	A-1.3	10/A-1.6	Concrete under neighbour fence post	200	10%	2 19	CF	
27	A-1.3	Note-16/A-1.8 1/A-1.6	Concrete footing under 36" high CMU wall #5 @ 18" O.C each way #5 hooks continue up minimum @ 32" O.C	200	10%	2 20	CF	
28	A-1.3	Legend/A-1.3 4A/A-1.6	Concrete footing under 12" CMU wall #5 @ 18" O.C each way #5 hooks continue up minimum @ 32" O.C	30	10%	3 3	CF	
29	A-1.3	14/A-1.7	Concrete footing under 16"x16" column -#5 bars @ 12" O.C Each way, top &	19	10%	2 0	CF	
30	A-1.3	11/A-1.7	Concrete footing under 2'-8"X 2'-8" column -#5 bars @ 12" O.C Each way, top & bottom (4) #5 hook base continue upto column minimum 2 cells	57	10%	6 3	CF	
31	A-1.3	9/A-1.7	Concrete footing 2'X2' under column -#5 bars @ 12" O.C Each way, top & bottom (4) #5 hook base continue upto column minimum 2 cells	37	10%	4 0	CF	
			BUILDING A CONCRETE					
			F4 Column					
32	S2.0A	Footing schedule	F4 Column concrete w/ (4) #4 bars each way at bottom	96	10%	1 06	CF	
			F3 Column					
33	S2.0A	Footing schedule	F3 Column concrete w/ (3) #4 bars each way at bottom	41	10%	4 5	CF	
			Grade beam					
34	S2.0A	5/S5.0	Grade beam w.r.t section-5 w/ -(2) #5 bars at top & bottom -(#4) ties @ 12" O.C	####	10%	####	CF	
			Grade beam					
35	S2.0A	6/S5.0	Grade beam w.r.t section-6 -(2) #5 bars at top & bottom -(#4) ties @ 12" O.C at 12" O.C	438	10%	4 82	CF	
			Grade beam					
36	S2.0A	21/S5.0	Grade beam w.r.t section-21 -(3) #5 bars at top & bottom -(#4) ties @ 12" O.C at 12" O.C	198	10%	2 18	CF	
			SLAB ON GRADE					
37	S2.0A	S2.1A	5" Slab on grade w/ #4 at 18" O.C each way	945	10%	####	SF	
38	S2.0A	S2.1A	4" clean crush gravel	312	10%	3 43	CF	
			SLAB ON GRADE					
39	S2.0A	S2.1A	5" Slab on grade w/ #4 at 18" O.C each way	672	10%	7 39	SF	

40	S2.0A	S2.1A		2" Sand layer	114	10%	1 26	CF
41	S2.0A	S2.1A		10 mil reinf. Vapor barrier	672	10%	7 39	SF
42	S2.0A	S2.1A		4" clean crushed gravel	222	10%	2 44	SF
				CONTROL JIONT				
43	S2.0C	4/S5.0		Key-form w/ SHP'D. 2x-6" long w/ spaced at 2'-0" O.C 1/2" dia x 2'-0" long smooth dowels spaced at 12" O.C	234	10%	2 57	LF
				BUILDING B CONCRETE				
				F4 Column				
44	S2.0B	Footing schedule		F4 Column concrete w/ (4) #4 bars each way at bottom	120	10%	1 32	CF
				F3 Column				
45	S2.0B	Footing schedule		F3 Column concrete w/ (3) #4 bars each way at bottom	122	10%	1 34	CF
				F2 Column				
46	S2.0B	Footing schedule		F2 Column concrete w/ (2) #4 bars each way at bottom	12	10%	1 3	CF
				Grade beam				
47	S2.0B	5/S5.0		Grade beam w.r.t section-5 w/ -(2) #5 bars at top & bottom -(#4) ties @ 12" O.C	####	10%	####	CF
				Grade beam				
48	S2.0B	6/S5.0		Grade beam w.r.t section-6 -(2) #5 bars at top & bottom -(#4) ties @ 12" O.C at 12" O.C	372	10%	4 09	CF
				Grade beam				
49	S2.0B	21/S5.0		Grade beam w.r.t section-21 -(3) #5 bars at top & bottom -(#4) ties @ 12" O.C at 12" O.C	216	10%	2 38	CF
				SLAB ON GRADE				
50	S2.0A	S2.1A		5" Slab on grade w/ #4 at 18" O.C each way 4" clean crush gravel	####	10%	####	SF
51	S2.0A	S2.1A		SLAB ON GRADE	360	10%	3 96	CF
52	S2.0A	S2.1A		5" Slab on grade w/ #4 at 18" O.C each way 2" Sand layer	828	10%	9 11	SF
53	S2.0A	S2.1A		10 mil reinf. Vapor barrier	141	10%	1 55	CF
54	S2.0A	S2.1A		4" clean crushed gravel	828	10%	9 11	SF
55	S2.0A	S2.1A		CONTROL JIONT	278	10%	3 06	CF
				Key-form w/ SHP'D. 2x-6" long w/ spaced at 2'-0" O.C 1/2" dia x 2'-0" long smooth dowels spaced at 12" O.C	312	10%	3 43	LF
				BUILDING C CONCRETE				
				F4 Column				
				F4 Column concrete w/ (4) #4 bars each way at bottom	72	10%	7 9	CF
				F3 Column				
				F3 Column concrete w/ (3) #4 bars each way at bottom	230	10%	2 52	CF
				F2 Column				
				F2 Column concrete w/ (2) #4 bars each way at bottom	8	10%	9	CF
				F3.5 Column				
				F3 Column concrete w/ (4) #4 bars each way at bottom	18	10%	2 0	CF
				Grade beam				
				Grade beam w.r.t section-5 w/ -(2) #5 bars at top & bottom -(#4) ties @ 12" O.C	####	10%	####	CF
				Grade beam				

62	S2.0C	6/S5.0		Grade beam w.r.t section-6 -(2) #5 bars at top & bottom -(#4) ties @ 12" O.C at 12" O.C	906	10%	9 97	CF	
				SLAB ON GRADE					
63	S2.0C	S2.1A		5" Slab on grade w/ #4 at 18" O.C each way	####	10%	####	SF	
64	S2.0C	S2.1A		4" clean crush gravel	361	10%	3 97	CF	
				SLAB ON GRADE					
65	S2.0C	S2.1A		5" Slab on grade w/ #4 at 18" O.C each way	####	10%	####	SF	
66	S2.0C	S2.1A		2" Sand layer	249	10%	2 74	CF	
67	S2.0C	S2.1A		10 mil reinf. Vapor barrier	####	10%	####	SF	
68	S2.0C	S2.1A		4" clean crushed gravel	483	10%	5 31	CF	
				CONTROL JOINT					
69	S2.0C			Key-form w/ SHP'D. 2x-6" long w/ spaced at 2'-0" O.C 1/2" dia x 2'-0" long smooth dowels spaced at 12" O.C	350	10%	3 85	LF	
				Sub Total					
				CONCRETE CURB & GUTTER					
70	A-1.3	3/A-1.6		Concrete curb along driveway	304	10%	3 34	LF	
71	A-1.3	6/A-1.6		Concrete curb & gutter along sidewalk	127	10%	1 40	LF	
72	A-1.3	Note-6/A-1.3 & 3/A-1.6		Concrete curb along guest parking	61	10%	6 7	LF	

