

**PROJECT ADDRESS**  
 Date of submis  
 Date of plans  
 Scope  
**MASONRY**

KEY QUANTITIES		
8" CMU	867	SF
Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE		UNIT	REFERENCE	TOTAL COST
						TE	WASTE			
<b>04 00 MASONRY</b>										
<b>BLOCK MASONRY</b>										
<b>TRASH ENCLOSURE</b>										
<b>8" CMU WALL</b>										
1	A-1.13	A-1.13		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ Bond Beam	3 92	10%	4 31	SF		\$ -
2	A-1.13	A-1.13		(2) #5 Continuous Bar <b>Scaffolding</b>	4 9	10%	54	LF		\$ -
3	A-1.13	A-1.13		Half height Scaffolding	4 9	10%	54	LF		\$ -
<b>PATIO AREA</b>										
<b>8" CMU WALL</b>										
4	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 24" O.C	2 13	10%	2 34	SF	\$ -	\$ -
5	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	5 0	10%	55	LF	\$ -	\$ -
6	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area	5 0	10%	55	LF		\$ -
<b>8" CMU WALL</b>										
7	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 32" O.C	1 84	10%	2 02	SF	\$ -	\$ -
8	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	6 0	10%	66	LF	\$ -	\$ -
<b>SUB TOTAL</b>										\$ -
<b>STONE CAP</b>										
<b>PATIO AREA</b>										
9	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area on 8" CMU Wall	5 0	10%	55	LF		\$ -
<b>SUB TOTAL</b>										\$ -
<b>VENEER @ FIRE PIT</b>										
<b>BRICK VEENER @ FIRE PIT</b>										
10	A-1.14	A-1.14		Brick Veneer @ Fire Pit	2 13	10%	2 34	SF		\$ -
11	A-1.14	A-1.14		Pre Fab Top with Slate Tile (01 Each)	1 7	10%	18	SF		\$ -
<b>SUB TOTAL</b>										\$ -

**PROJECT ADDRESS**  
 Date of submis  
 Date of plans  
 Scope  
**MASONRY**

KEY QUANTITIES		
	867	SF
Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	UNIT	REFERENCE	REFERENCE	TOTAL COST
				<b>CRAFT VENEER MASONRY</b>						
				<b>PATIO AREA</b>						
12	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	4 26	10%	4 69	SF		\$ -
13	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	4 20	10%	4 62	SF	\$ -	\$ -
14	A-1.13	A-1.13		Scaffolding	4 20	10%	4 62	SF		\$ -
<b>SUB TOTAL</b>										\$ -
15	A-1.12	A-1.12		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	3 95	10%	4 35	SF		\$ -
16	A-1.12			Scaffolding	3 95	10%	4 35	SF	\$ -	\$ -
<b>SUB TOTAL</b>										\$ -
17	A-2.01	3/A5.01		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	2 26	10%	2 49	SF	\$ -	\$ -
18	A-1.12			Scaffolding	3 02	10%	3 32	SF	\$ -	\$ -
<b>SUB TOTAL</b>										\$ -
19	A-2.01	2/A-7.04		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	3,699	10%	4,069	SF		\$ -
20	A-1.12			Scaffolding	4,111	10%	4,523	SF	\$ -	\$ -
<b>SUB TOTAL</b>										\$ -
21	A-2.01			ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	6 51	10%	7 16	SF	\$ -	\$ -
22	A-1.12			Scaffolding	8 91	10%	9 80	SF	\$ -	\$ -
<b>SUB TOTAL</b>										\$ -

<b>PROJECT ADDRESS</b>										
Date of submis										
Date of plans										
Scope										
<b>MASONRY</b>										

KEY QUANTITIES		
	867	SF
Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	UNIT	REFERENCE	REFERENCE	TOTAL COST
23	A-2.01	1/A-5.02, 3/A5.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	2,232	10%	SF	\$ -	\$ -	
24	A-2.01			Scaffolding	4,038	10%	SF	\$ -	\$ -	
<b>METAL COPPING</b>										
25	A-1.13	A-1.13		Metal Copping @ Trash Enclouser	49	10%	LF	\$ -	\$ -	
26	A-1.11	A-1.11		Metal Copping @ Patio area	15	10%	LF	\$ -	\$ -	
27	A-2.01			Metal Copping @ East Elevation	40	10%	LF	\$ -	\$ -	
28	A-2.01			Metal Copping @ North Elevation	44	10%	LF	\$ -	\$ -	
29	A-2.01			Metal Copping @ West Elevation	150	10%	LF	\$ -	\$ -	

