

PROJECT  
 ADDRESS  
 Date of plans  
 Comments  
 TOTAL BASE BID



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST
				<b>RAILING</b>						
				<b>ARCHITECTURAL SITE PLAN</b>						
				<b>BUILDING 1</b>						
				<b>TREE PIT GUARD RAILING</b>						
1	A035.00	K1/A068.00		1/2" X 1-1/2" Top rail	113	10%	124	LF	\$ -	\$ -
2	A035.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	113	10%	124	LF	\$ -	\$ -
3	A035.00	K1/A068.00		1'-0"H 1/2" sq picket assumed at 6" O.C.	226	0%	226	EA	\$ -	\$ -
4	A035.00	K1/A068.00		1'-6"H 2" sq solid steel post	16	0%	16	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 2</b>						
				<b>TREE PIT GUARD RAILING</b>						
5	A036.00	K1/A068.00		1/2" X 1-1/2" Top rail	81	10%	89	LF	\$ -	\$ -
6	A036.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	81	10%	89	LF	\$ -	\$ -
7	A036.00	K1/A068.00		1'-0"H 1/2" sq picket	163	0%	163	EA	\$ -	\$ -
8	A036.00	K1/A068.00		1'-6"H 2" sq solid steel post	16	0%	16	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 3</b>						
				<b>TREE PIT GUARD RAILING</b>						
9	A037.00	K1/A068.00		1/2" X 1-1/2" Top rail	21	10%	23	LF	\$ -	\$ -
10	A037.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	21	10%	23	LF	\$ -	\$ -
11	A037.00	K1/A068.00		1'-0"H 1/2" sq picket	42	0%	42	EA	\$ -	\$ -
12	A037.00	K1/A068.00		1'-6"H 2" sq solid steel post	4	0%	4	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 4</b>						
				<b>TREE PIT GUARD RAILING</b>						
13	A038.00	K1/A068.00		1/2" X 1-1/2" Top rail	101	10%	111	LF	\$ -	\$ -
14	A038.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	101	10%	111	LF	\$ -	\$ -
15	A038.00	K1/A068.00		1'-0"H 1/2" sq picket	202	0%	202	EA	\$ -	\$ -
16	A038.00	K1/A068.00		1'-6"H 2" sq solid steel post	20	0%	20	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 5</b>						
				<b>TREE PIT GUARD RAILING</b>						
17	A038.00	K1/A068.00		1/2" X 1-1/2" Top rail	90	10%	99	LF	\$ -	\$ -
18	A038.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	90	10%	99	LF	\$ -	\$ -
19	A038.00	K1/A068.00		1'-0"H 1/2" sq picket	180	0%	180	EA	\$ -	\$ -
20	A038.00	K1/A068.00		1'-6"H 2" sq solid steel post	20	0%	20	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 6</b>						
				<b>Guard Rail at Flood Wall</b>						

PROJECT  
 ADDRESS  
 Date of plans  
 Comments  
 TOTAL BASE BID



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST
21	A040.00	A1, A5 /A-063		Guard Rail <b>Note: The plan do not show Guard Rail but the details show guard rail. Even on the detail, the information is insufficient. Please confirm,</b>	408	10%	449	LF	\$ -	\$ -
				<b>BARUCH DRIVE</b>						
				<b>Hand Rail at Stair</b>						
22	A040.00	G1/A-064		1 1/2" S.S Dia hand rail	58	10%	64	LF	\$ -	\$ -
23	A040.00	G1/A-064		3'-0"H Steel post	16	10%	18	EA	\$ -	\$ -
				<b>Hand Rail at Ramp</b>						
24	A040.00	K11/A-063		1 1/2" S.S Dia hand rail	237	10%	260	LF	\$ -	\$ -
				<b>Guard Rail at Ramp</b>						
25	A040.00	K11/A-063		3'-6"H Aluminium wire mesh guard rail w/ Aluminium framed panel	121	10%	133	LF	\$ -	\$ -
26	A040.00	K11/A-063		3'-6"H Galvanized Steel posts W/ Welded closed top	24	0%	24	EA	\$ -	\$ -
27	A040.00	K11/A-063		5x5x1/4" S.S plate welded with S.S steel post	48	0%	48	EA	\$ -	\$ -
28	A040.00	K11/A-063		1x1x1/8"x1" Long galvanized steel L'S welded to tube & guard rail	24	0%	24	EA	\$ -	\$ -
				<b>DELANCY STREET</b>						
				<b>Hand Rail at Stair</b>						
29	A040.00			1 1/2" S.S Dia hand rail	62	10%	69	LF	\$ -	\$ -
30	A040.00			3'-6"H Steel post	16	10%	18	EA	\$ -	\$ -
				<b>Hand Rail at Ramp</b>						
31	A040.00	B1/A-063		LED illuminated 1 1/2" S.S Dia hand rail	66	10%	73	LF	\$ -	\$ -
32	A040.00	B1/A-063		3'-0"H Steel post	15	0%	15	EA	\$ -	\$ -
				<b>Guard Rail at Ramp</b>						
33	A040.00	k6/A-063		3'-6"H Aluminium wire mesh guard rail w/ Aluminium framed panel	208	10%	229	LF	\$ -	\$ -
34	A040.00	k6/A-063		3'-6"H Galvanized Steel posts W/ Welded closed top	42	0%	42	EA	\$ -	\$ -
35	A040.00	k6/A-063		5x5x1/4" S.S plate welded with S.S steel post	84	0%	84	EA	\$ -	\$ -
36	A040.00	k6/A-063		1x1x1/8"x1" Long galvanized steel L'S welded to tube & guard rail	42	0%	42	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 7</b>						
				<b>TREE PIT GUARD RAILING</b>						
37	A041.00	K1/A068.00		1/2" X 1-1/2" Top rail	149	10%	164	LF	\$ -	\$ -
38	A041.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	149	10%	164	LF	\$ -	\$ -
39	A041.00	K1/A068.00		1'-0"H 1/2" sq picket	298	0%	298	EA	\$ -	\$ -
40	A041.00	K1/A068.00		1'-6"H 2" sq solid steel post	32	0%	32	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -

PROJECT  
 ADDRESS  
 Date of plans  
 Comments  
 TOTAL BASE BID



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST
				<b>BUILDING 8,9</b>						
				<b>TREE PIT GUARD RAILING</b>						
41	A041.00	K1/A068.00		1/2" X 1-1/2" Top rail	160	10%	176	LF	\$ -	\$ -
42	A041.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	160	10%	176	LF	\$ -	\$ -
43	A041.00	K1/A068.00		1'-0"H 1/2" sq picket	320	0%	320	EA	\$ -	\$ -
44	A041.00	K1/A068.00		1'-6"H 2" sq solid steel post	32	0%	32	EA	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>BUILDING 10</b>						
				<b>TREE PIT GUARD RAILING</b>						
45	A043.00	K1/A068.00		1/2" X 1-1/2" Top rail	280	10%	308	LF	\$ -	\$ -
46	A043.00	K1/A068.00		1/2" X 1-1/2" Bottom rail	280	10%	308	LF	\$ -	\$ -
47	A043.00	K1/A068.00		1'-0"H 1/2" sq picket	560	0%	560	EA	\$ -	\$ -
48	A043.00	K1/A068.00		1'-6"H 2" sq solid steel post	56	0%	56	EA	\$ -	\$ -
				<b>BARUCH DRIVE</b>						
				<b>Hand Rail at stair</b>						
49	A043.00	E14/A-064		LED Illuminated 1-1/2" S.S Dia hand rail	57	10%	63	LF	\$ -	\$ -
50	A043.00	E14/A-064		3'-0" Steel post	12	10%	13	EA	\$ -	\$ -
				<b>Hand Rail at Ramp</b>						
51	A043.00	J8/A-064		1 1/2" S.S Dia hand rail	213	10%	235	LF	\$ -	\$ -
				<b>Guard Rail at Ramp</b>						
52	A043.00	J8/A-064		3'-6"H Aluminium wire mesh guard rail w/ Aluminium framed panel	113	10%	124	LF	\$ -	\$ -
53	A043.00	J8/A-064		3'-6"H 3x3x1/4" Galvanized Steel posts W/ Welded closed top	23	0%	23	EA	\$ -	\$ -
54	A043.00	J8/A-064		0'-8"H 2x2x1/4" Galvanized Steel posts bolted w 3" Sq post	23	0%	23	EA	\$ -	\$ -
55	A043.00	J8/A-064		5x5x1/4" S.S plate welded with S.S steel post	46	0%	46	EA	\$ -	\$ -
				<b>Guard Rail at Flood wall</b>						
56	A043.00	C7/A-064		3'-6"H Aluminium wire mesh guard rail w/ Aluminium framed panel	261	10%	287	LF	\$ -	\$ -
57	A043.00	C7/A-064		3'-6"H 3x3x1/4" Galvanized Steel posts W/ Welded closed top	52	0%	52	EA	\$ -	\$ -
58	A043.00	C7/A-064		0'-8"H 2x2x1/4" Galvanized Steel posts bolted w 3" Sq post	52	0%	52	EA	\$ -	\$ -
59	A043.00	C7/A-064		5x5x1/4" S.S plate welded with S.S steel post	104	0%	104	EA	\$ -	\$ -
60	A043.00	C7/A-064		1x1x1/8"x1" Long galvanized steel L'S welded to tube & guard rail	52	0%	52	EA	\$ -	\$ -